BRUHAT BANGALORE MAHANAGAR PALIKE

Project Division, Yelahanka Zone

SCHEDULE - B

Improvements to drains of roads next to Ayyappa temple of Jakkur Layout in ward no.07 and Improvements to drains of cross roads of Jakkur layout in ward no.07, Byatarayanapura

SNo	Quantity	Item Name	Unit	Rates quoted by Sri. U RAMESH	
				In figures	In words
1	599.70	Earthwork excavation by manual means in rodinary soil involving an average horizontal throw upto 2 m and an average lift upto 1.5m, excavated surafce levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking clods complete as per specifications..	cum	150.96	Rupees One Hundred Fifty And Paise Ninety Six Only
2	107.83	Providing and laying in position plain cement concrete of nominal mix 1:4:8 using 40mm and down size graded granite metal machine mixed, conrete laid in layers not exceeding 15 cms. Thick well compacted in foundation and plinth, including cost of all materials labour, HOM of machinery, curing complete as per specification	cum	5924.60	Rupees Five Thousand Nine Hundred Twenty Four And Paise Sixty Only
3	239.85	Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320 Kgs with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum with superplastizers @ 3lts confirming to IS 9103-1999 RE affirmed - 2008 machine mixed, concrete laid in layers not exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, stair case lintels, retaining walls return walls, walls(anythickness) including attached plasters columns piers abutments pillars posts struts butresses string or lacing courses parapets copings, bed blocks , plain windows cills fillets etc., including cost of all materials labour HOM of machinery curing complete as per specifications	cum	6571.40	Rupees Six Thousand Five Hundred Seventy One And Paise Forty Only
4	14.39	Providing TMT Steel Reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications	tonne	82407.85	Rupees Eighty Two Thousand Four Hundred Seven And Paise Eighty Five Only
5	1968.00	Providing and removing Centering, shuttering, strutting, propping etc., for columns, pillars, piers, abutments, post and struts, square / rectangular slabs /side walls polygon in plan including cost of materials, labour complete as per specification and directions of the Engineer in charge	sqm	425.01	Rupees Four Hundred Twenty Five And Paise One Only
6	14.40	Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240 kgs, with 20 mm and down size graded granite matel coarse aggregates @ 0.69 cum and fine aggragtes @ 0.459cum, machine mixed concrete laid in layers not eceeding 15 cms, thick well compacted, in foundation, plinth and cills including cost of all materials, labour HOM machinery curing complate as per specifications.	cum	6318.25	Rupees Six Thousand Three Hundred Eighteen And Paise Twenty Five Only

U. Ramesh
Contractor

Executive Engineer
Project Division
Yelahanka Zone

	Quantity	Item Name	Unit	Rates quoted by Sri. U RAMESH	
				In figures	In words
7	1025.00	Providing and fixing 10cms thick pre cast RCC covering slab using reinforced cement concrete M20 mix with stone aggregate 20mm and down size including centring shuttering reinforcement and bar bending machine mixed concrette laid in layers not exceeding 15 cm thick wellcompacted cost of all materials labour curing complete as per specfications (Data Rate Approved)	sqm	2300.55	Rupees Two Thousand Three Hundred And Paise Fifty Five Only
8	60.00	Providing and fixing MS Grating 260x260 mm	nos	97.50	Rupees Ninety Seven
9	599.70	Loading and unloading of stone boulder/stone aggregates/ sand/ kanker/ moorum. KSRRB M100-1:Placing tipper at loading point loading with front end loading, dumping turning for return trip, excluding time for haulage and return trip complete as per specification MORTH Chapter 1	cum	103.35	Rupees One Hundred Three And Paise Thirty Five Only
10		GST @ 12%			

U. Ramesh
Contractor

Executive Engineer
Project Division
Yelahanka Zone